

석면비산측정 결과보고서

- 도초 테마가 있는 웰빙소공원
[수국공원(수국온실)조성]지정폐기물 철거공사 -

[별 첨1] 측정 위치도(측정 장소)

전라남도 신안군 도초면 도초서길 246-11



범 례



부지경계선

*NO

시료채취

[별첨2] 측정 결과

2014. 09. 01.					
측정위치		측정시간(분)	유량(l/min)	측정농도 [기준: 0.01개/cm ³]	초과여부
*1	부지경계선1	14:30 ~ 18:32	9.96	불검출[검출한계 0.002미만]	미만
*2	부지경계선2	14:31 ~ 18:33	9.94	불검출[검출한계 0.002미만]	미만
*3	부지경계선3	14:33 ~ 18:35	9.97	불검출[검출한계 0.002미만]	미만
*4	부지경계선4	14:34 ~ 18:36	9.98	불검출[검출한계 0.002미만]	미만
*5	위생설비입구	14:36 ~ 15:18	9.94	0.002	미만
*6	작업장주변	14:38 ~ 15:20	9.96	불검출[검출한계 0.002미만]	미만
*7	폐기물야적	14:40 ~ 15:22	9.98	불검출[검출한계 0.002미만]	미만
*8	음압기배출구1	14:43 ~ 15:25	9.97	0.003	미만
*9	음압기배출구2	14:46 ~ 15:28	9.93	0.002	미만
*10	음압기배출구3	14:48 ~ 15:30	9.97	불검출[검출한계 0.002미만]	미만

[별첨3] 측정 사진

2014. 09. 01.

				
*1 부지경계선1	*2 부지경계선2	*3 부지경계선3	*4 부지경계선4	*5 위생설비입구
				
*6 작업장주변	*7 폐기물야적	*8 음압기 배출구1	*9 음압기 배출구2	*10 음압기 배출구3